HIGHLAND PERGOLA KIT

Tools Required

Layout and Measuring

☐	**Tape Measure**		
☐	**Framing Square**		
☐	**Level**		
☐	**Chalk Line**		
☐	**Laser Level / Rotary Laser**	Optional but recommended for determining any difference in elevations at the post bases.	OPTIONAL

Drilling and Fastening

☐	**Drills / Impact Drivers**		
☐	**Torx Bit Set**		
☐	**1 ⅜" Dia. Drill Bit**	Used for drilling out the bottom of the posts for the post bases.	
☐	**1" Dia. Drill Bit**	Used for drilling out tenons for pegs.	
☐	**Hammer Drill**		IF ON CONCRETE
☐	**3/8” Concrete Bit**		IF ON CONCRETE

Cutting and Fitting

☐	**Circular Saw**		
☐	**Hand Saw**		
☐	**Chisel Set**		

Access and Lifting

☐	**Ladders x2**		
☐	**Lifting Device**	Heavy equipment isn’t required, but something like a Genie SLC lift allows for safe lifting of the timbers. These can be rented.	RECOMMENDED